

BOQ Calculation for Auditorium

Item No	Description	Unit	Quantity	Unit Rate(BDT)	Total Amount
1	Cable works				
	4x1C-50mm2 NYY(BRB Cables)	Meter	176	3,383.83	595,554.08
	4x1C-25mm2 NYY(Bizli Cables)	Meter	1250	2,116.40	2,645,500.00
	4x1C-4mm2 NYY	Meter	321	415.40	133,343.40
	4x1C-4mm2 NYY	Meter	66	415.40	27,416.40
2	Cable works (ECC)				
	1x1c-16mm2 BYA	Meter	180	196.40	35,352.00
	1x1c-16mm2 BYA	Meter	1270	196.40	249,428.00
	1x1c-4mm2 BYA	Meter	330	25.58	8,441.40
	1x1c-4mm2 BYA	Meter	75	25.58	1,918.50
3	Circuit Breakers				
	160A TP MCCB	Each	3	7,500.00	22,500.00
	80A DP MCB	Each	15	1,200.00	18,000.00
	32A DP MCB	Each	15	310.00	4,650.00
	32A DP MCB	Each	14	310.00	4,340.00
	10A DP MCB	Each	11	260.00	2,860.00
	20A TP MCB	Each	14	427.00	5,978.00
4	Air condition				
	Central AC	Each	13	264,000.00	3,432,000.00
	1.5 TON AC	Each	4	57,900.00	231,600.00
5	Busbar				
	300A (20x10)mm2 Cu Busbar	meter	6	2,700.00	16,200.00
6	Lights				
	Tube light (TL)	Each	15	1,220.00	18,300.00
	Mirror light (M)	Each	14	620.00	8,680.00
	Stage Spot Light(SL)		3	11,577.00	34,731.00
	Garden light (G)		3	389.00	1,167.00
	Door Light(D)		2	189.00	378.00
	Exhibition Spot Light (SP)		3	621.00	1,863.00
	Flat LED Light (FL)		10	2,400.00	24,000.00
	Ceiling light (CL)		35	1,450.00	50,750.00
	Stage Light(StL)		3	17,500.00	52,500.00
7	Fans				
	1440 mm2 cealing fan	Each	4	2,000.00	8,000.00
8	Sokets				
	3 Pin 13 A socket	Each	10	375.00	3,750.00
	2 pin 5A socket	Each	13	35.00	455.00
9	Switchs				
	1 way 4 gang 10A switch	Each	156	400.00	62,400.00
10	Conduit				
	Minimum inner Dia. 20 mm & minimum wall thickness 1.5 mm.	meter	1426	40.00	57,040.00
	Minimum inner Dia. 25 mm & minimum wall thickness 1.5 mm.	meter	421	55.00	23,155.00
				Total Cost	7,782,250.78